

D-1 BID FORM

PROJECT A –MENTOR ROAD #2

Item 1: Asphalt Overlays

Street Name	Length (Ft.)	Begin	End	Width (Ft.)	Area (Sq. Yd.)	Compacted Thickness (In.)	Estimated Tons
Mentor Road	9,091	Airbase Road	Town Limit Northeast along Mentor Road	18	18,182	1.5	1483.0

Item 2: Shoulder Stone

Street Name	Linear Ft.	Description
Mentor Road	18,182	All overlay areas in Item 1. Apply stone to eliminate edge drop-off as needed.

Item 3: Shoulder Maintenance

Street Name	Linear Ft.	Description
Mentor Road	18,182	Re-grade and dress shoulders as needed to restore runoff flow away from entire length Mentor Road

Item 4: Pavement Striping

Street Name	Linear Ft.	Description
Mentor Road	9,091	Reapplying the double yellow centerline and white road edge marking to the roadway surface. The marking will consist of two parallel 4-inch yellow painted lines separated by a 4-inch gap and one 4-inch white painted lines on each road edge (two white total).

PROJECT B – ROBINSON DRIVE

Item 1: Asphalt Overlays

Street Name	Length (Ft.)	Begin	End	Width (Ft.)	Area (Sq. Yd.)	Compacted Thickness (In.)	Estimated Tons
Robinson Drive	1846	Topside Road	Johnston Road	34	6,974	1.5	568.8

Item 2: Curb Maintenance

Street Name	Linear Ft.	Description
Robinson Drive	3,692	Clean curb grass and debris as needed to restore runoff flow away from entire length of Robinson Drive.

PROJECT B – ROBINSON DRIVE

BID BASIS ITEM 1 = TONS OF ASPHALT OVERLAY IN PLACE

BID _____ APPROXIMATE TOTAL TONS

\$ _____ PER TON

BID BASIS ITEM 2 = LINEAR FEET SHOULDER MAINTENANCE

BID _____ APPROXIMATE TOTAL LINEAR FEET

\$ _____ PER LINEAR FOOT

BIDDER: _____ (print name)

_____ (signature)

Date _____

PROJECT C – MENTOR ROAD #1 DRAINAGE IMPROVEMENTS

Item 1: Asphalt Overlays

Street Name	Length (Ft.)	Begin	End	Width (Ft.)	Area (Sq. Yd.)	Compacted Thickness (In.)	Estimated Tons
Mentor Road	300	Mentor Road	Mentor Road	18	600	1.5	48.9

Item 2: Shoulder Stone

Street Name	Linear Ft.	Description
Mentor Road	600	All overlay areas in Item 1. Apply stone to eliminate edge drop-off as needed.

Item 3: Drainage Improvements

Street Name	Lot	Description
Mentor Road		All improvements shown on drawing CD1 dated January 09, 2020

Item 4: Pavement Striping

Street Name	Linear Ft.	Description
Mentor Road	300	Reapplying the double yellow centerline and white road edge marking to the roadway surface. The marking will consist of two parallel 4-inch yellow painted lines separated by a 4-inch gap and one 4-inch white painted lines on each road edge (two white total).

